



- *pipes 3,4,5 & B,C,D,E,F must be stable & must not move when spring panels attached to them are impacted by performers
- *grid should be 1.5" schedule 40 steel pipe or nearest metric size equivalent
- *grid pipes trim at +3.7m unless otherwise noted